

**CITY OF SCHERTZ, TEXAS  
EAST LIVE OAK WATER PLANT PUMP UPGRADES  
City Project #12-ENG-39-C-04  
Engineers Project 1124.8411**

**ADDENDUM NO. 1**

**Date of Addendum: October 19, 2012**

**TO: Prospective Bidders**

Be advised that this Addendum No.1 affects the following changes in the Contract Documents:

**CONTRACT DOCUMENTS**

**INVITATION TO BIDDERS:**

No change.

**SPECIFICATIONS:**

Section 11310.2.3. Materials: Pedestal and Subbase to be fabricated steel. Can is fabricated steel.

**PLANS:**

Sheet 3 of 8 – “HS-7” Should read “HSP-4”

**QUESTIONS AND ANSWERS**

Q1: Section 11310.1.8 of the specifications refer to the following types of testing: 1) Performance, 2) Hydrostatic, 3) NPSH, 4) Priming Time, 5) Vibration Test, 6) IEEE Motor Test. Which of these will be required?

A1: Results for all tests should be provided by the manufacturer.

Q2: Can you clarify the existing can/barrel dimensions?

A1: The existing can/barrel for LSP-1 is 24 inches diameter and 17.9 feet from flange to bottom. The existing can/barrel for HSP-4 is 30 inches and 17.9 feet from flange to bottom. This information is based on the as-built plans from the original construction.

**Acknowledgement by Bidder**

Each bidder is requested to acknowledge receipt of this Addendum No.1 by his/her signature affixed hereto and to file it with and attached to his/her bid.

The undersigned acknowledges receipt of this Addendum No. 1, and that the bid submitted herewith is in accordance with the information and stipulations set forth.

\_\_\_\_\_  
Date

\_\_\_\_\_  
Signature of Bidder

\_\_\_\_\_  
Typed or Printed Name